



No. 8017/2015/NIQ/11

Dated 04.07.2015

**NOTICE INVITING QUOTATIONS (Second Call)**

Sealed Item Rates quotations for the below mentioned work are hereby invited by the undersigned from approved and eligible Contractors/Firms/Individuals having experience of similar work in central govt./State govt. department/Institution on or before 10.07.2015 at 3.00 pm and the same will be opened on the same day at 3:30pm.

The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned.

SI No	NAME OF WORK	EST. COST in`	E.M.D in`	TIME
1	Providing LPG pipe line work for modular lab in Department of pathology & lab medicine at AIIMS Raipur.	1,43,820.00	NIL	20 Days

**SCHEDULE OF QUANTITY**

Sl.	Description of items	Quantity	Rate	Unit	Amount
.....As PER SHEET ATTACHED.....					

Terms & Conditions:

1. Quotation shall only be issued on application to eligible to Contractors upto one day before scheduled date of opening.
2. The rates are to be quoted in words and figures including all taxes.
3. The work will be executed as per CPWD specifications and direction of the Engineer-In Charge.
4. The payment will be done after completion of work as per specification.
5. Time allowed for the completion of the work is 20 (Twenty) Days. It will be reckoned from the day award of the work.

(Signature of Contractor)

Issued to M/s /Shri\_\_\_\_\_

Executive Engineer  
Project Cell  
AIIMS, Raipur

**SCHEDULE OF QUANTITY**

Name of Work : LPG pipe line for modular lab in Department of Pathology at AIIMS Raipur					
S.N.	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
1	Providing and Fixing MANIFOLD (made by mild steel )c class 25.4mm(1"dia) size 3*3(3' length), centre distance between the consecutive lugs shall be 350mm(14") or 425mm(17")	No.	1		
2	Providing and Fixing ADAPTER SKN made-ADST25/HPC or equivalent (high pressure regulator) the multi point locking system,25.6mm collar and outlet 21.8*1.81 SI LH	No.	3		
3	Providing and Fixing CYLINDER PIGTAIL HPC ,Suraksha or equivalent made by wire braided rubber hose of 8mm Dia. Bore, length 60".Fitted with brass nuts at both ends.	No.	3		
4	Providing and Fixing SHUT OFF VALVE Pune Gas Plant and series Ltd. Or equivalent for lock and unlock Dia.15mm.	No.	2		
5	Providing and FixingAdjustable LPG Regulator HPC or equivalent (presetlpg regulator) for constant pressure in pipeline, inlet pressure (0.35kgf/cm <sup>2</sup> -10.0kgf/cm <sup>2</sup> ),delivery pressure 0.035kgf/cm <sup>3</sup> to 1.4kgf/cm <sup>3</sup>	No.	1		
6	Providing and FixingPRESSURE GAUGE (SKN or Equivalent)for correct pressure of gas in pipe line with indicate pressure of 0.5 to 20 psi	No.	1		
7	Providing and FixingNEEDLE CONTROL VALVE ,3/8" BSPTM x 3/8"cu.(HPC or equivalent) made with brass forging for controlling flow of gas to high pressure points.	No.	6		
8	Providing and Fixing HIGH TO LOW ADAPTER (SKN FTR 3/8" or equivalent) with delivery pressure 20-80 mbar.	No.	6		
9	Providing and Fixing COPPER PIPE GI cylinder pigtail ,1.5 Copper Pipe with both side brass nut made by brass 3/8" dia)	No.	6		
10	Providing and Fixing SOCKET ,3/8" Socket with inner thread.	No.	43		
11	Providing and Fixing TERMINAL BLOCK 2 way (fitted on table of lab with in let at base & nozzle /tap.	No.	30		
12	Providing and Fixing TapLever type (Pune Gas Plant and series Ltd. Modle B-1 Or equivalent)made by brass for on /off.	No.	60		
13	Providing and Fixing TERMINAL PATTI, Terminal Patti made by ms plate (2.5" dia) for hold for terminal in table	No.	30		

14	Providing and Fixing BENSON BURNER, length 150mm.	No.	60		
15	Providing and Fixing GAS RUBBER PIPE , 1.5 metre Yash pipe made by rubber Dia. 8mm	No.	30		
16	Providing and Fixing CLAMP,Manifold Clamp (Bak)(1") made by msFlat.	No.	2		
17	Providing and Fixing MS CLAMP (Saddle)for½ " pipe.	No.	50		
18	Providing and Fixing ½" Bull Nose MECV.	Set	50		
19	Providing and Fixing E.R.W. ½inch C ClassPipe (Gindal or Equivalent)	Metre	100		
20	Providing and Fixing BRASS NUT,½ inch Brass nut made by brass with both side thread, 3/8"bsptm*3/8" cu	No.	4		
21	Providing and Fixing MAIN LINE COPPER PIPE 3'to connect in main line pipe, made by brass with both side brass ends 1/2" dia	No.	2		
22	Providing and Fixing MAIN LINE VALVE (making Valve of HPC or equivalent)1/2"BSPTM x MECV.	No.	1		
23	Providing and Fixing NON RETURN VALVES (Three Pcs)of HPC or Equivalent FECU x MECV.Maximum working pressure 200bars, end connection 1/2"-2' bspint/ ext as per regulator ,made by brass.	No.	3		

(Signature of the Agency)

EXECUTIVE ENGINEER  
PROJECT CELL, AIIMS RAIPUR