



No. 8017/2015/NIQ/15

Dated 06.07.2015

SHORT NOTICE INVITING QUOTATIONS

Sealed Item Rates quotations for the below mentioned work are hereby invited by the undersigned from approved and eligible Contractors of appropriate class registered in CPWD,DOP, MES, BSNL, Railways, Chhattisgarh State PWD (B&R)so as to reach this office on or before 09.07.2015 at 3.00 pm and the same will be opened on the same day at 3:30pm.

The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned.

SI No	NAME OF WORK	EST. COST in Rs.	E.M.D in Rs.	TIME
1	Dismantling work of Stone slab with RCC Slab and Brick pillars to installation of the kitchen items at NSH mess at AIIMS Raipur.	34,151.00	NIL	3 Days

SCHEDULE OF QUANTITY

Sl.	Description of items	Quantity	Rate	Unit	Amount
.....As PER SHEET ATTACHED.....					

Terms & Conditions:

1. Quotation shall only be issued on application to eligible to Contractors up to one day before scheduled date of opening.
2. The rates are to be quoted in words and figures including all taxes.
3. The work will be executed as per CPWD specifications and direction of the Engineer-In Charge.
4. The payment will be done after completion of work as per specification.
5. Time allowed for the completion of the work is 20 (Twenty) Days. It will be reckoned from the day award of the work.

(Signature of Contractor)

Issued to M/s /Shri_____

Executive Engineer
Project Cell
AIIMS, Raipur

SCHEDULED OF QUANTITY

<u>Name of Work</u> - Dismantling work of Stone slab with RCC Slab and Brick pillars to installation of the kitchen items at NSH mess at AIIMS Raipur.					
Sr.	Item	Unit	Qty	Rate	Amount
1	Demolishing R.C.C. work manually/by mechanical means including disposal of unserviceable material within 50 meters lead as per direction of Engineer - in- charge.	cum	6		
2	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge				
a	In cement mortar	cum	10		
3	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50metres lead.	sqm	30		
4	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade Two or more coats on new work	sqm	15		
5	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead :With cement mortar 1:4 (1cement: 4 coarse sand)	sqm	12.488		
6	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand)	sqm	10		

(Signature of the Agency)

Executive Engineer
Project Cell,AIIMS Raipur