



अखिल भारतीय आयुर्विज्ञान संस्थान, रायपुर (छत्तीसगढ़)
All India Institute of Medical Sciences, Raipur (Chhattisgarh)
Tatibandh, GE Road,
Raipur-492 099 (CG)
www.aiimsraipur.edu.in

No. 8017/2015/ NIQ/23

Dated 25.08.2015

NOTICE INVITING QUOTATIONS

Sealed Item Rates quotations for the below mentioned work are hereby invited by the undersigned from approved and eligible Contractors of appropriate class registered in CPWD,DOP, MES, BSNL, Railways, Chhattisgarh State PWD (B&R)so as to reach this office on or before 28.08.2015 at 3.00 pm and the same will be opened on the same day at 3:30pm.

The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned.

SI No	NAME OF WORK	EST. COST in ₹	E.M.D in ₹	TIME
1	Electrical Works for the installation of 3 phase supply with MCCB to start Horizontal Autoclave machine in Dressing and Plaster Room at 3 rd Floor Room No. 34 in Trauma Building.	36,008/-	NIL	03 Days

SCHEDULE OF QUANTITY

Sl.	Description of items	Quantity	Rate	Unit	Amount
.....As PER SHEET ATTACHED.....					

Terms & Conditions:

1. The rates are to be quoted in words and figures including all taxes, octroi, transportation etc.
2. The work will be executed as per CPWD specification and direction of the Engineer-in-Charge.
3. The payment shall be done for the work done & recorded.
4. Time allowed for the completion of the work is 02 (Two) Days.
5. Labour laws shall be complied by the agency.
6. Quotation papers shall be issued to the eligible Contractor.

(Signature of Contractor)

Issued to M/s /Shri_____

Executive Engineer
Project Cell
AIIMS, Raipur

Schedule of Quantity

Name of Work :- Electrical Works for the installation of 3 phase supply with MCCB to start Horizontal Autoclave machine in Dressing and Plaster Room at 3rd Floor Room No. 34 in Trauma Building.

1	2	3	4	5	6	7	8	9	10	
S.NO.	DESCRIPTION OF ITEM	UNIT	QTY	Make	Rate	With Tax (5%)	Labour	With Tax (15%)	Amount	
1	Supply & laying of 16 sq.mm * 4 core Aluminium armored cable of 1.1 kv grade with complete installation with earth wire.	Meter	70	Polycab						
2	Supply & Installation of 32/ 40 Amp MCCB 4Pole, 35KA	Nos.	1	L&T						
3	Supply of Heavy duty Exhaust fan of 450mm sweep.	Nos.	1	CGL						
	Total Amount as per Contractor included with all taxes.									

(Signature of Contractor)

Issued to M/s /Shri _____

Executive Engineer
Project Cell
AIIMS, Raipur