



अखिल भारतीय आयुर्विज्ञान संस्थान, रायपुर (छत्तीसगढ़)

All India Institute of Medical Sciences, Raipur (Chhattisgarh)

Tatibandh, GE Road,

Raipur-492 099 (CG)

www.aiimsraipur.edu.in

Ph.0771-2572930, e-mail: se@aiimsraipur.edu.in

No: 54(8017) SE/AIIMS/RPR/2015-16/NIQ/27

Date: 18/03/2016

NOTICE INVITING QUOTATIONS

Sealed Item Rates quotations for the below mentioned work are hereby invited by the undersigned from approved and eligible Contractors/Firms/Individuals having experience of similar work in central govt./State govt. department/Institution on or before Date:28/03/2016 at 3.00 PM and the same will be opened on the same day at 3:30 PM. The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned. The quotation papers can be seen/downloaded from the website www.aiimsraipur.edu.in and same may be issued from the office of The Superintending Engineer, AIIMS Raipur during the hours of 10:00 AM to 5:00 PM every day except on Sunday & public holiday upto 28/03/2016 at 3.00 PM.

SI No	NAME OF WORK	EST. COST ₹	E.M.D ₹	TIME
1	Proper Fixation of Foundation Stone of AIIMS Raipur	59701.00	Nil	30 Days

SCHEDULE OF QUANTITY

Sl.	Description of items	Quantity	Rate	Unit	Amount
.....As PER SHEET ATTACHED.....					

ADDITIONAL CONDITION:-

1. Payment shall be made for the quantity measured & recorded in MB, nothing extra will be considered for payment.
2. All the material, equipment, labour and safety arrangement etc. will be arranged by the contractor. Nothing will be issued by the department.
3. Work is of urgent nature and should be completed within Thirteen (30) Days after award of work.
4. The work shall be carried out as per CPWD specification with upto corrections slips and terms and conditions of work order.
5. Agency shall comply the labour rules.
6. All statutory taxes deduction shall be made as per provisions.

(Signature of Contractor)

Issued to M/s /Shri _____

Executive Engineer
AIIMS, Raipur

SCHEDULE OF QUANTITY

Name of Work: - Proper Fixation of Foundation Stone of AIIMS Raipur.

SL No	Description	Qty	Unit	Rate in `		Amount
				In Figure	In Words	
1	MARBLE WORK					
1.1	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.					
1.1.1	Granite of any colour and shade					
1.1.1.1	Area of slab upto 0.50 sqm	1.5	sqm			
1.1.1.2	Area of slab over 0.50 sqm	2	sqm			
1.2	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.					
1.2.1	Marble work	3	metre			
1.2.2	Granite work	3	metre			
1.3	Mirror polishing on marble work/Granite work/stone work where ever required to give high gloss finish complete.	10	sqm			
1.4	Stone tile (polished) work for wall lining over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and cement slurry @ 3.3 kg/sqm including pointing in white cement complete.					
1.4.1	8mm thick					
1.1.1.1	Granite of any colour and shade	3	sqm			
1.5	Providing and fixing machine cut, mirror/ eggshell polished , Marble stone work for wall lining (vener work) including dado, skirting, risers of steps etc., in required design and pattern wherever required, stones of different finished surface texture, on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 oarse sand) laid and jointed with white cement slurry @ 3.3 kg/sqm including pointing with white cement slurry admixed with pigment of matching shade, including rubbing, curing, polishing etc. all complete as per Architectural drawings, and as directed by the Engineer-in-Charge.a. 18 mm thick	3	sqm			

	Italian Marble stone slab,Perlato, Rosso verona, Fire Red or Dark Emperadore etc.					
2	In graving work on marble/stone as per direction of Engineer in charge.	200	Each Words			
3	Letter writing on marble/stone as per direction of Engineer In charge.	200	Each Words			
4	Excavating holes more than 0.10 cum & up to 0.5 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc, disposing of surplus excavated soil, as directed within a lead of 50 m and lift upto 1.5 m. [a] all kinds of soil.	5	each			
5	Supplying & filling black cotton/ good earth in excavated hole for plants.	5	each			
6	Supply and planting of healthy trees (Average 5 feet height) as given below: Free from diseases and of specified types and caliper and maintaining the same for a period of 3 months from the date of plantation including stacking of trees and replacement of any casualty/defective plants during the maintenance period complete.					
6.1	SESHAM	1	each			
6.2	GUL MOHAR	1	each			
6.3	MUSUNDA	1	each			
6.4	CROTAN	1	each			
6.5	CHINA PALM	1	each			
	NOTE: The list of trees given above is tentative and can be changed as per the site requirement. The list is given herewith to give general idea of the kind of plant materials or similar that would be used and is only for tendering/ quotation purpose.					
TOTAL						

(Signature of Contractor)

Executive Engineer
AIIMS, Raipur