



अखिल भारतीय आयुर्विज्ञान संस्थान, रायपुर (छत्तीसगढ़)
All India Institute of Medical Sciences, Raipur (Chhattisgarh)
Tatibandh, GE Road,
Raipur-492 099 (CG)
www.aiimsraipur.edu.in

No. 8017/2015/NIQ/24

Dated 31.08.2015

NOTICE INVITING QUOTATIONS (REVISED)

Sealed Item Rates quotations for the below mentioned work are hereby invited by the undersigned from approved and eligible Contractors/Firms/Individuals having experience of similar work in central govt./State govt. department/Institution on or before 08.09.2015 at 3.00 pm and the same will be opened on the same day at 3:30 pm. The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned. The quotation papers can be received from this office upto 08.09.2015 (1.00PM)

SI No	NAME OF WORK	EST. COST in Rs.	E.M.D in Rs.	TIME
1	Cleaning of water tanks at Medical college, NSH, BH, Nursing college, Ayush –PMR Building, Trauma Building and Hospital Administrative Block at AIIMS Raipur.	62230.00	Nil	30 Days

SCHEDULE OF QUANTITY

Sl.	Description of items	Quantity	Rate	Unit	Amount
.....As PER SHEET ATTACHED.....					

ADDITIONAL CONDITION:-

1. Payment shall be made for the quantity measured & recorded in MB, nothing extra will be considered for payment.
2. All the material, equipment, labour and safety arrangement etc. will be arranged by the contractor. Nothing will be issued by the department.
3. Work is of urgent nature and should be completed within Thirteen (30) Days after award of work.
4. The work shall be carried out as per CPWD specification with upto corrections slips and terms and conditions of work order.
5. Agency shall comply the labour rules.
6. All statutory taxes deduction shall be made as per provisions.

(Signature of Contractor)

Issued to M/s /Shri _____

Executive Engineer
Project Cell
AIIMS, Raipur

SCHEDULE OF QUANTITY

Name of Work: - Cleaning of water tanks at Medical college, NSH, BH, Nursing College, Ayush –PMR Building, Trauma Building and Hospital Administrative Block at AIIMS Raipur.

Item No.	Sub-heads and Item of Work	Quantity	Unit	Rate	Amount
1.1	Cleaning of soft water tank, Domestic water tank, Flushing water tank and Fire tanks by scrubbing the peripheral wall surface floor and ceiling with suitable high pressure jet sprayer to remove all mineral/biological deposit including any micro organism, Silts sand clay etc. and by spraying with jet sprays chemicals like silver Nitrate/Hypochlorite/Potassium permanganate/Iodine/Ethyl alcohol diluted to permissible limit, rinse the surface of tank with clean potable water and remove all wash water and sediments from all the surface with vacuum cleaner and section pumps and disinfectioning with ultra-violet rays the internal area, The process includes dewatering the balance left water in sumps over head tank by means of electrical pumps of suitable capacity before commencing cleaning of tank i/c marking the date of cleaning by Black Japan paints of visible size complete as per direction of Engineer-in-Charge (A) PVC/Ferro cement concrete/RCC Terrace tank in Hospital/College Buildings.				
1.1.1	For Capacity up to 1000 litre.	1	Each		
1.1.2	For Capacity 1001 litre to 5000 litre tank.	17	Each		
1.1.3	For Capacity 5001 litre to 10000 litre tank.	2	Each		
1.1.4	For Capacity 10001 litre to 20000 litre tank.	4	Each		
1.1.5	R.C.C. water storage tank from 20001 to 30000 litre capacity.	1	Each		
1.1.6	R.C.C. water storage tanks from 30001 to 45000 litre capacity.	3	Each		
				Total	

(Signature of Contractor)

Executive Engineer
Project Cell
AIIMS, Raipur