



Store/Work/ Electrical/Blood Bank/2015 AIIMS-RPR

Date: 01.06.2015

**Inviting Quotations for Electrical works for Dept. Of Transfusion Medicine(Blood bank) at AIIMS, Raipur**

**QUOTATION NOTICE**

Sealed quotations are invited from intending registered contractors having TIN and relevant documents for electrical work at **Dept. Of Transfusion Medicine(Blood bank) at AIIMS, Raipur** should be submitted to office of Store officer up to 03.06.2015, before 3:00 pm the quotations will be opened on the same day at 03.15pm. Details of item are given as under:-

S.NO.	DESCRIPTION OF ITEM	UNIT	QTY	Unit Rate in ₹
1	Wiring for circuit/submain wiring along with earth wire with the following size of 1.1kV Grade FRLS PVC insulated copper conductor, single core multistrand cable in surface / recessed medium class PVC conduit as required.			
a	2 x 4 sq.mm + 1 x 4 sq.mm earth wire	Meter	60	
b	4 x 4 sq.mm + 2 x 4 sq.mm earth wire	Meter	100	
c	4 x 10 sq. mm + 2 x 6 sq.mm earth wire	Meter	30	
2	Supplying & fixing of suitable size GI box with modular plate & cover in front on surface or in recess, including providing & fixing 6 pin 15/16 amps modular socket outlet & 15/16 amps modular switch, connections etc. as required	Each	15	
3	Supplying & fixing following way prewired TP&N MCB distribution board of steel sheet for 415 volts on surface/recess complete with loose wire box, terminal connectors for all incoming & outgoing circuits, duly prewired with suitable size FRLS PVC insulated copper conductor up to terminal blocks, tinned copper bus bar, neutral link, earth bar, din bar, detachable gland plate, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)			
a	6 way (4+18), Double door	Each	1	
4	Supplying & Fixing of 5amps to 32 amps rating, 240/415 volts "C" curve, miniature circuit breaker suitable for inductive load of following poles in existing MCB DB complete with connections, testing & commissioning etc. as required.			
a	Single Pole	Each	18	
5	Supplying & Fixing of 415volt TPN MCB in the existing MCB DB complete with connection, testing & commissioning etc.	Each	1	

- Taxes, if any (Kindly Mention).
- Work should be complete within 3 to 7 days from the date of issue of work order.
- Price should be for- Destination basis.

- d) LD @ 0.5% of PO value per week or Part of week for delay of completion of work subject to maximum up to 10% of PO value.
- e) Tender no. should be mentioned on top of envelop.

Store Officer  
AIIMS, Raipur (C.G.)