

अखिल भारतीय आयुर्विज्ञान संस्थान, रायपुर (छत्तीसगढ़)

All India Institute of Medical Sciences, Raipur (Chhattisgarh)

Tatibandh, GE Road, Raipur-492 099 (CG) www.aiimsraipur.edu.in

Tender enquiry no. ADMIN/Tender/Barricading/1/2013

Corrigendum for Barricading Tender

Clause	Old	Updated
page no. 4 /col. No.2 'Description of Item'	Providing corrugated GI sheet barricading of 0.63 mm thick sheets with zinc coating not less than 275 gm/Sqm fixed with polymer coated J or L hooks ,bolts, nuts 8mm dia with bitumen and GIIimpet washers or with GI limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets and one side complete. Sheets to be fixed on 50mm vertical and 40 mm horizontal MS pipes with necessary clamps. Rates to include cost of providing all material and underground holding arrangement e.g excavation, concrete and backfilling etc. Barricading shall be the property of contractor after the work completion. Pitch of MS pipes shall be 2m in horizontal direction and 1m in vertical direction.	"Providing 8' (2.44 m) high corrugated GI sheet (Min. thickness 0.63 mm) barricading fixed with GI hooks & nuts on frame made of MS Pipes having dia. not less than 40 mm. Barricading shall be painted on one side as decided with one coat of primer and two coats of synthetic enamel paint of approved brand and colour. Spacing of vertical pipes shall not be less than 3 m (Average) and min two horizontal pipes shall be provided. Rate shall be inclusive of cost of providing all material and fixing arrangements e.g excavation, concrete and backfilling etc. and removal of the complete barricading after requirement is over. (Material of Barricading shall be the property of contractor after the work completion)".
page no. 2 Point No.2	Experience in the work of providing Security Services. Particulars of experience (Attach certificates, testimonials). This shall cover the details of works of similar nature, approximate magnitude and duration carried out and/or on hand for last 3 years along with a certificate from the organisation where the job was carried out.	Experience in the civil work. Particulars of experience (Attach certificates, testimonials). and/or on hand for last 3 years along with a certificate from the organisation where the job was carried out.

Following points are also to be noted as addendum:

- (1) The GI sheets used should be of good condition and it should not be rusted, torn, bend and shall be got approved before using in the work,
- (2) Notwithstanding the specification mentioned herein the Barricading including support should be strong enough to withstand wind pressure and remain in proper position during the contract period.



अखिल भारतीय आयुर्विज्ञान संस्थान, रायपुर (छत्तीसगढ़)

All India Institute of Medical Sciences, Raipur (Chhattisgarh) Tatibandh, GE Road,

Raipur-492 099 (CG) www.aiimsraipur.edu.in

- (3) The contractor shall keep barricading in good condition during the whole contract period including extended period and the rate include its maintenance for any damages, painting, all incidentals, labour materials, equipments and works required to execute the job.
- (4) Payment shall be made @ 70% after satisfactory installation. Remaining 30% shall be paid after removal.(Applicable for both stipulated and extended period, if any)
- (5) The rate for the extended period shall be fixed @10% of the accepted rate for each 3 months or part of the extended period beyond stipulated period.
- (6) The work shall be divided into separate, distinguishable segments for sake of measurements and payment and payment shall be made for these segments after their satisfactory installation. Their period shall start from their respective date of installation.

Administrative Officer AIIMS, Raipur