



No. 8017/2015/NIQ/18

Dated 09.07.2015

SHORT NOTICE INVITING QUOTATIONS

Sealed Item Rates quotations for the below mentioned work are hereby invited by the undersigned from approved and eligible Contractors of appropriate class registered in CPWD,DOP, MES, BSNL, Railways, Chhattisgarh State PWD (B&R)so as to reach this office on or before 13.07.2015 at 3.00 pm and the same will be opened on the same day at 3:30pm.

The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned.

SI No	NAME OF WORK	EST. COST in Rs.	E.M.D in Rs.	TIME
1	Brick work & finishing work in substation 3&4 in Main Hospital Building at AIIMS Raipur.	26987.00	NIL	3 Days

SCHEDULE OF QUANTITY

Sl.	Description of items	Quantity	Rate	Unit	Amount
.....As PER SHEET ATTACHED.....					

Terms & Conditions:

1. Quotation shall only be issued on application to eligible to Contractors up to one day before scheduled date of opening.
2. The rates are to be quoted in words and figures including all taxes.
3. The work will be executed as per CPWD specifications and direction of the Engineer-In Charge.
4. The payment will be done after completion of work as per specification.
5. Time allowed for the completion of the work is 20 (Twenty) Days. It will be reckoned from the day award of the work.

(Signature of Contractor)

Issued to M/s /Shri_____

Executive Engineer
Project Cell
AIIMS, Raipur

ABSTRACT OF COST

Name of Work: Brick work & finishing work in substation 3 &4 in Main Hospital Building at AIIMS Raipur.

Sr.no	Description of item	Qty	Unit	Rate	Amount
1	Brick work with non modular fly ash bricks conforming to IS:12894, class designation 10 average compressive strength in super structure above plinth level up to floor V level in :Cement mortar 1:6 (1 cement : 6 Coarse sand)	3.00	cum		
2	12 mm cement plaster of mix,1:6 (1 cement: 6 fine sand)	7	sqm		
3	15 mm cement plaster of mix, 1:6 (1 cement: 6 fine sand)	7	sqm		
4	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :Water thinnable cement primer	15	sqm		
5	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade				
a	Two or more coats on new work	60	sqm		
6	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	15	sqm		

(Signature of the Agency)

Executive Engineer
Project Cell,AIIMS Raipur