



अखिल भारतीय आयुर्विज्ञान संस्थान, रायपुर (छत्तीसगढ़)
All India Institute of Medical Sciences, Raipur (Chhattisgarh)
Tatibandh, GE Road,
Raipur-492 099 (CG)
www.aiimsraipur.edu.in

No. 8017/2015/ NIQ/22

Dated 11.08.2015

NOTICE INVITING QUOTATIONS

Sealed Item Rates quotations for the below mentioned work are hereby invited by the undersigned from approved and eligible Contractors of appropriate class registered in CPWD,DOP, MES, BSNL, Railways, Chhattisgarh State PWD (B&R)so as to reach this office on or before 14.08.2015 at 3.00 pm and the same will be opened on the same day at 3:30pm.

The right to reject any or all the quotations without assigning any reasons thereof shall rest with undersigned.

Sl No	NAME OF WORK	EST. COST in ₹	E.M.D in ₹	TIME
1	Plantation of Trees in the campus of AIIMS Raipur including 6 months maintenance period.	90,226/-	NIL	03 Days

SCHEDULE OF QUANTITY

Sl.	Description of items	Quantity	Rate	Unit	Amount
.....As PER SHEET ATTACHED.....					

Terms & Conditions:

1. The rates are to be quoted in words and figures including all taxes, octroi, transportation etc.
2. The work will be executed as per CPWD specification and direction of the Engineer-in-Charge.
3. The payment shall be done for the work done & recorded.
4. Time allowed for the completion of the work is 02 (Two) Days & maintenance shall be carried out 6 month from date of start of work.
5. Labour laws shall be complied by the agency.
6. Quotation papers shall be issued to the eligible Contractor.

(Signature of Contractor)

Issued to M/s /Shri_____

Superintending Engineer
Project Cell
AIIMS, Raipur

Schedule of Quantity

NAME OF WORK: Plantation of Trees in the campus of AIIMS Raipur including 6 months maintenance period.

Sr.No.	Perticulars	qty	unit	rate	amount
1	Excavating holes more than 0.10 cum & upto 0.5 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc, disposing of surplus excavated soil,as directed within a lead of 50 m and lift upto 1.5 m. [a] all kinds of soil.	120	each		
2	supplying & filling black cotton/ good earth in excavated hole for plants.	120	each		
3	Supplying & planting of healthy trees sapling as given below, free from diseases etc.				
a	ASHOKA	40	each		
B	SESHAM	10	each		
C	GUL MOHAR	10	each		
D	MUSUNDA	10	each		
E	CROTAN	12	each		
F	NEEM	12	each		
G	CHINA PALM	12	each		
H	PELTAFARM	14	each		
4	Watering of , plants, trees i/c uprooting grass, weeds etc at a suitable interval by keeping one skilled Mali for performing above activities i/c maintain the plants by providing dump manure fertilizers, pesticides as per requirement of plants complete as per direction of AIIMS authority.	6	MONTHS		
